

1 080242

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-21,307.0000

N/2 SW NE, SEC. 7, T 21 S, R 14 W/E  
3630 feet from N SE Corner of ~~XXX~~ section line  
1980 feet from W SE Corner of ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Frey Well # 1

Operator: F & M Oil Co., Inc.

County Stafford

Name & Address 422 Union Center

Well Total Depth 3710 <sup>120' SX</sup> feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 909

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:00 am Day: 24 Month: October Year: 19 84

Plugging proposal received from Joe Maize

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 3709' Perfs at 3404-08 & 3411-18' PBTD 3575

1st plug sand back to 3350' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 10 sx gel, 50 sx cement, 10 sx gel, 4 sx hulls, and 150

sx cement.

Plugging Proposal Received by J. H. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:40 am Day: 24 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 3709' Perfs at 3404-08 & 3411-18' PBTD 3575'

1st plug sanded back to 3350' and dumped 4 sx cement on top of sand through bailer

2nd plug squeezed well with 10 sx gel, 50 sx cement, 10 sx gel, 4 sx hulls, and 150

sx cement.

STATE CORPORATION COMMISSION

NOV 31 1984 10-31-84

Maximum pressure 300 psi and shut in pressure 200 psi

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Recovered 80' of dropped 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed J. Metz SWD  
(TECHNICIAN)

INVOICED

DATE 11-2-84

INV. NO. 4630