

1 080200

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION N/2 SE SE , SEC. 9 , T 21 S, R 14 W/4
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,550

990 FSL feet from ~~XXX~~ section line N SE Corner of
660 FEV feet from ~~XXX~~ section line W SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 8446

Lease Name Powell Well # 2-9

Operator: Producers Operating Co., Inc.
Name & Address Pioneer Plaza/Two, Suite 200
Amarillo, TX 79101

County Stafford

Well Total Depth 3850 125.13 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 436

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 22 Month: August Year: 19 84

Plugging proposal received from Byron Clawson

(company name) Rockhold (phone) 316-792-2506

were: 5 1/2" set at 3849' PBTB 3850'

1st plug sand back to 3590' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump an additional 130 sx cement.

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 am Day: 22 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 3849' PBTB 3850'

1st plug sanded back to 3590' and dumped 5 sx cement on top of sand through bailer.

2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

released 8 5/8" rubber plug and pumped an additional 130 sx cement.

Maximum pressure 550 psi and shut in pressure 300 psi

Remarks: They recovered 2390' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-7-84

INV. NO. 3582

CONSERVATION DIVISION
Wichita, Kansas

Signed J. H. Metz (TECHNICIAN)

9-4-84