

1-080559

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 100'
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,365-0000
NW SE SE ^{SE} SEC. 9, T 21 S, R 14 W/E
380 feet from S section line
380 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8446
Operator: Producers Operating Co., Inc.
Name & Address Box 9833
Amarillo, TX 79105

Lease Name Powell Well # 1-9
County Stafford 121.81
Well Total Depth 3748 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 329

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 25 Month: 10 Year: 19 86

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering (phone) 316-792-2506

were: 5 1/2" at 3746' PBD 3710' Perfs at 3642-52'

1st plug sand back to 3580' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:20 a.m. Day: 25 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3580' and dumped 5 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and pumped 125 sx cement.

Maximum pressure 300 psi and shut in 0 psi. 10-28-86

Remarks: Used 60/40 Pozmix 6% gel by Allied. OCT 28 1986

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not observe this plugging.)

DATE 10-28-86

Signed J. A. [Signature]
(TECHNICIAN)

INV. NO. 15253

10-25