

To: 1 120463
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-11 15-195-20145-00-02
API NUMBER 15-E-23,281
SW NW NE, SEC. 9, T 21 S, R 14 W/E
4290 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9339
Operator: K & K Oil
Name & Address: Box 176
Chase, KS 67524

Lease Name Asher Well # B-4
County Stafford 113.75
Well Total Depth 3500 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 422

Abandoned Oil Well Gas Well Input Well X SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 11 Month: 9 Year: 19 90

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 3498', Perfs at 3440-45'

1st plug sand back to 3300' and dump 4 sx cement on top of sand through bailer,

2nd plug circulate cement from 600' through tubing with 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1 p.m. Day: 11 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3300' and dumped 4 sx cement on top of sand through bailer,

2nd plug circulated cement from 600' with 150 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 616' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (copy / maintain) observe this plugging.

DATE 9-25-90

INV. NO. 29421

9-11

Signed Steve Durrant (TECHNICIAN)

STATE RECEIVED 9-18-90
SEP 18 1990
WICHITA, KANSAS