

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 7 Twp. 21S Rge. 11W (E) (W)

Location as "NE/CNW/SW" or footage from lines 330' From S&E Lines NW/4

Lease Owner Sinclair Oil & Gas Company

Lease Name ~~THOMAS OLIVE OP~~ Olive Opie Well No. 1

Office Address Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 9-2-50 19

Application for plugging filed 1-16-61 19

Application for plugging approved 2-17-61 19


Plugging commenced 5-8-61 19

Plugging completed 5-16-61 19

Reason for abandonment of well or producing formation Exhausted oil well -
Unprofitable to operate.

If a producing well is abandoned, date of last production 5-4-61 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Rank Broadfoot

Producing formation Arbuckle Lime Depth to top 3701 Bottom 3712 Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle Lime	Oil	3701	3712	7"	3700'	2628
				10-3/4"	898'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded bottom of hole from 3712 to 3690', dumped 5 sacks cement to 3670' with dump bailer, Mudded hole from 3670' to 260', 10' rock bridge from 260 to 250', 25 sacks cement from 250' to 190', mud from 190' to 35', 10' rock bridge to 25', 10 sacks cement from 25' to surface. Completed P&A at 4:PM 5-16-61.

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
C. E. Most (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.E. Most, Dist. Supt.
P. O. Box 446, Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 19 61

My commission expires August 13, 1962
L. B. Reynolds Notary Public

15.185.01858.0000

COPY OF DRILLER'S LOG

Sinclair Oil & Gas Company
Olive Opie # 1
Sec 7-21S-11W
Stafford, County, Kansas

Contractor;
Holm Drlg. Co.
Wichita, Kansas

Surface Casing
898' of 10-3/4" 40# Casing
Cemented with 450 sacks

GEOLOGICAL TOPS FROM ELECTRIC LOG

Brown Lime	3353'
Lan. KC	3366'
Conglomerate	3615'
Viola	3617'
Simpson	3656'
Arbuckle	3701'
Total Depth	3712'

Date Std. drilling 8-22-1950
Date Completed drilling ~~start~~ 9-2-1950

Long String;
7" 23# casing set at 3700'
cemented with 200 sacks.

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1961

CONSERVATION DIVISION
Wichita, Kansas