


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

T - 21 NORTH R - 14W



Locate well correctly on above Section Plat

Stafford County, Sec. 7 Twp. 21 Rge. 14 (E) W (W)  
Location as "NE/CNWxSWx" or footage from lines SW SW NE  
Lease Owner Frank J. Black  
Lease Name Frey Well No. 1  
Office Address McPherson, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 7-13-50 19  
Application for plugging filed 5-22-62 19  
Application for plugging approved 5-23-62 19  
Plugging commenced 6-7-62 19  
Plugging completed 6-9-62 19  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3727 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	866'	None
				5-1/2"	3720'	3254'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3727', sanded to 3710' and dumped 5 sacks of cement @ 3710' with dump bailer. Pulled 5 1/2" casing. Mudded hole to 260', set 10' rock bridge to 250' and ran 20 sacks of cement @ 250'. Mudded to 35', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 18 1962

PLUGGING COMPLETE.

CONSERVATION DIVISION  
Wichita, Kansas

6-18-1962

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of June, 19 62

My commission expires May 20, 1964

Milton J. Volin  
Notary Public.

COPY


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 E. Murdock Wichita, Kansas

Company - THE VICKERS PETROLEUM CO., INC.  
Farm - Frey No. 1

SEC: 7 T. 21 R. 14W  
S7 S7 NE

Total Depth. 3727  
Comm. 6-16-50 Comp. 7-13-50  
Shot or Treated.  
Contractor.  
Issued. 9-2-50

County. Stafford  
KANSAS



Elevation. 1935 R.B.

Production. Pot. Drawdown 2392  
BOPD & NW

CASING:

8 5/8" 866' cem. w/400 sx  
5 1/2" 3720' cem. w/75 sx

Figures indicate Bottom of Formations.

sand & shalo	150
shalo & shells	250
shalo, shells & sand	320
sand	430
redbed & shalo	500
redbed	885
anhydrite	920
shalo & shells	1445
salt, shalo & shells	1620
broken limo	1930
broken lime & sand	2075
limo & shalo	2165
broken limo	2405
limo & shalo	3293
shalo	3361
lime & shale	3629
cherty conglomerate	3634
chert	3666
shale & sand	3718
dolomite	3727
Total depth	

Tops:

Hoebner	3261
Brown lime	3361
Lansing	3378
Conglomerate	3629 Corr.
Viola	3634 "
Simpson	3666 "
Arbuckle	3718 "

Remarks:

SIM 3722 -25  
DST 3719 -3725  
Open 30 min. rec. 180' heavily  
oil cut mud. B.H.P. 1070 $\frac{1}{2}$ .  
Drld. plug clean out to 3725'  
Fillup 700' oil in 2 $\frac{1}{4}$  hrs.  
Swab. 10 BO 1 hr, no wtr.  
Fillup 3000' oil in 15 hrs.  
DD to 3727  
Run tubing and acidize thru  
tubing w/500 gal.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 18 1962

CONSERVATION DIVISION  
Wichita, Kansas