


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 9 Twp. 21S Rge. 14 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NW
Lease Owner Dor-Bet and Thunderbird Drilling, Inc.
Lease Name Asher Well No. 1
Office Address 1311 Union Nat'l Bank Bldg, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-6 19 54
Application for plugging filed 9-6 19 54
Application for plugging approved 9-6 19 54
Plugging commenced 9-6 19 54
Plugging completed 9-6 19 54
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production - - - - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 3682 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		843'	85,8"	Surface Casing cemented with 365 sacks cement 3 calcium chloride 2% jel.		
		No oil	string			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug @ 270' with 1/2 sack hulls and 20 sacks cement. Top plug @ 35' with 1/2 sack hulls and 10 sacks cement.

RECEIVED
CORPORATION COMMISSION
SEP 10 1954
CONSERVATION DIVISION
Wichita, Kansas

9-10-54

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Thunderbird Drilling, Inc.
Address 1311 Union Nat'l Bank Bldg., Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. W. Owen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1311 Union Nat'l Bank Bldg. (Address)

SUBSCRIBED AND SWORN to before me this 9th day of September, 1954.

[Signature] Notary Public.

My commission expires August 25, 1956

PLUGGING
FILE SEC 9 T 21 R 14/W
BOOK PAGE 62 LINE 40

ASHER #1

LOCATION: SE SE NW Commenced: 8-25-54
 Sec. 9-21-S-14.W Completed: 9- 6-54
 Stafford County, Kansas

CONTRACTOR: Thunderbird Drilling, Inc.
 1311 Union Nat'l Bank Bldg.
 Wichita, Kansas

SURFACE CASING: 843' 8 5/8" cemented with
 365 sacks cement, 3 Calcium
 Chloride, 2% jel

OIL STRING: None

WELL LOG

0 -	200	Surface Sand
200 -	285	Shale
285 -	368	Sand
368 -	390	Red Bed
390 -	730	Shale, shells & red bed
730 -	837	Shale and shells
837 -	860	Anhydrite
860 -	1650	Shale and shells
1650 -	1775	Shale and lime
1775 -	2335	Lime
2335 -	2545	Lime and shale
2545 -	2805	Shale and shells
2805 -	2960	Shale and lime
2960 -	3225	Lime
3225 -	3320	Shale
3320 -	3573	Lime
3573 -	3595	Chert and lime
3595 -	3620	Simpson shale
3620 -	3645	Shale and lime
3645 -	3682	Lime
3682		Rotary Total Depth

The undersigned, J. W. Owen, an officer of Thunderbird Drilling, Inc., hereby certifies that the above is a true and correct log of the formations encountered in the drilling of the #1 Asher as shown in the daily drilling reports.

THUNDERBIRD DRILLING, INC.

J. W. Owen
J. W. Owen

Subscribed and sworn to before me this 9th day of Septmeber, 1954.

Leta Helm
Notary Public

My commission expires:
August 25, 1956

PLUGGING
 FILE SEC 9-21-S-14W
 BOOK PAGE 62 LINE 40

VED
 COMMISSION
 1954
 DIVISION
 Wichita, Kansas