

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 12 Twp. 21 Rge. 14 (E) 14 (W)

Location as "NE/CNW%SW%" or footage from lines NW SW NW/4

Lease Owner M. B. Armer

Lease Name Piel Well No. 1

Office Address 710 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Oct. 7, 1956

Application for plugging filed " " 19 " "

Application for plugging approved " " 19 " "

Plugging commenced " " 19 " "

Plugging completed " " 19 " "

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3695 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	296'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud 240 ft. 1/3 sack hulls,

set plug and cemented with 20 sacks through drill pipe.

Mudded hole to 35 ft., 1/3 sacks hulls, set plug and cemented

with 10 sacks cement to surface.

ARMER, Inc
ARTVILTY

Name of Plugging Contractor 710 PETROLEUM BLDG.

Address WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

E. C. Sponenberg (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. C. Sponenberg

(Address)

SUBSCRIBED AND SWORN to before me this 11 day of October, 19 56

My commission expires February 13, 1960.

Rose Furey

Notary Public.

PLUGGING
FILE SEC. 12 T. 21 R. 14W
BOOK PAGE 105 LINE 32

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1956
CONSERVATION DIVISION
Wichita, Kansas
10-12-56

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15.185.00937.0000

COMPANY **Herman Geo. Kelsner, et al**
 FARM **Piel** NO. **1**

SEC. **18** T. **21** R. **14W**
 LOC. **NW 34 NW**

TOTAL DEPTH **3695**
 COMM. **9/26/56** COMP. **10/7/56**
 SHOT OR TREATED
 CONTRACTOR **Armed, Inc.**
 ISSUED

COUNTY, **Stafford**
 KANSAS

CASING
 20 10
 15 8
 12 6
 13 5

ELEVATION **1923 U.S.**
 PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & Shells	230
Shale & Shells	296
Shale & Red Bed	350
Sand & Red Bed	403
Anhydrite	436
Red Bed, Shale & Shells	1050
Shale, Shells, Red Bed & Salt	1500
Shale & Lime	2165
Shale & Shells	2615
Shale, Shells & Lime	2850
Lime & Shale	3300
Lime	3501
Shale & Lime	3599
Chert	3617
Shale	3665
Lime	3695

FORMATION TOPS

NEEDY II	3221
NEEDY LINE	3337
LAWRENCE	3350
VIOLA	3598
SHERIDAN	3618
ANDERSON	3661

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMED, INC.

BY *L.P. Spradling*

BY STATE OF KANSAS
 COUNTY OF **STAFFORD**

Subscribed and sworn to before me, a notary public, in and for said County and State this 10th day of October, 1956.

Rose Turey
 Notary Public

My commission expires February 13, 1960.

PLUGGING

FILE SEC. 12 T. 21 R. 14W

BOOK PAGE 105 LINE 32

INDEXED
 OCT 12 1956
 DIVISION
 W. Kansas