


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Stafford County, Sec. 12 Twp. 21S Rge. 14W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines 75' SE of NW NW NE

Lease Owner Bell Oil Company
Lease Name Brown Well No. 1

Office Address 220 Rainbow Lake Road, Wichita, KS 67235

Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed August 30 1979
Application for plugging filed August 30 1979
Application for plugging approved August 30 1979
Plugging commenced August 30 1979
Plugging completed August 30 1979
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Owens, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2625
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged as follows:

Filled hole w/mud, pumped 40 sx 50/50 pozmix 2% gel, thru open end D.P. @ 360' mud to 40', 1/2 sx hulls & wood plug for solid bridge, pumped 12 sx to base of cellar, 3 sx in rathole - completed @ 9:45 a.m. by Sun 8-30-79;

Witnessed: Bill Owens, St. Pluggger, Pratt, Kansas
Gary Bagby, Sterling, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP - 5 1979

2-5-79

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Husky Drilling Co., Inc.

CONSERVATION DIVISION
Wichita, Kansas


STATE OF Kansas COUNTY OF Sedgwick, ss.
John S. Crowe (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
800 Bitting Building, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of September, 1979

Geraldine Stewart
Geraldine Stewart Notary Public.

My commission expires January 12, 1981



15.185.20953.0000



800 Bitting Bldg
Wichita, Kansas 67202
Phone 316 - 263-7904
Mobile Phone 316 - 793-7859 Unit 7070

September 4, 1979

WELL LOG-----Brown No. 1
Location: 75'SE of NW NW NE of Sec. 12-21S-14W
Stafford County, Kansas

OWNER: Bell Coil Company
ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: August 27, 1979
COMPLETED: August 30, 1979

Rotary Total Depth: 2625'

LOG

0 - 227 Sand
227 - 347 Shale
347 - 370 Red Bed
370 - 829 Red Bed & shale
829 - 850 Anhydrite
850 - 1725 Shale & shells
1725 - 2625 Shale & lime

CASING RECORD

Ran 9 jts., 8-5/8", 20#, 8Rd., Rge 3,
New casing, tallied 359.35', set @
366' KB w/275 sx 60/40 pozmix, 2% gel
3% cc - circulated - plug down @
5:15 p.m. by Sun - 8-27-79.

Plugged & abandoned 8-30-79.

RECEIVED
STATE CORPORATION COMMISSION
SEP - 5 1979
CONSERVATION DIVISION
Wichita, Kansas