

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-21,365.0000

LEASE NAME Powell

WELL NUMBER #1-9

430 Ft. from S Section Line

430 Ft. from E Section Line

SEC. 9 TWP. 21 RGE. 14 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 10-20-86

Plugging Completed 10-25-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Producers Operating, Co., Inc.

ADDRESS Box 9833, Amarillo, Texas 79105

PHONE# (405)-256-4544 OPERATORS LICENSE NO. 8446

Character of Well cil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ if not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3748'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	329'	None
				5-1/2"	3746'	2,597.81'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Dumped sand to 3580' and 5 sacks cement. Shot casing at 2800' and 2600'. Pulled 83 joints of 5-1/2" casing. Allied squeezed well with 2 sacks hulls, 15 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 125 sacks 60/40 pozmix cement with 6% added gel and 3% calcium chloride. Maximum pressure was 3000psi and shutin zero.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
 (Address) James W. Rockhold
Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 19 86

Rec'd
 11-4-86

My Commission Expires: NOV 4

STATE NOTARY PUBLIC
 IGNA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-87

Iona M. Leatherman
 Notary Public