

15.185.11360.0000

Form CP-3
Rev. 6-26-62

KL
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1963

CONSERVATION DIVISION
Wichita, Kansas

11-18-63

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Harter "A" Well No. # 3

Location SE NW SE Sec. 8 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3628

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Co.

Address: Route 2, Great Bend, Kansas License No.

Operation Completed: Hour 9:00AM Day 15th Month Nov. Year 1963

The Above well was plugged as follows:

327' of 8 5/8" surface pipe, cemented with 400 sacks. Fluid level was
up in hole. 1st cementing plug and 1/4 sack hulls was pushed to 300',
cemented with 25 sacks, through drill pipe. Hole was filled with drill-
ing mud to 40', 2nd cementing plug, bridged with 1/2 sack hulls, cemented
with 10 sacks to base cellar. Rat hole bridged and cemented with 2 sacks.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 11/19/63
INV. NO. 8136-4

Signed: Archie Elving
Well Plugging Supervisor