

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name L. K. Parrish

Complete Address: 714 Fourth National Bldg., Wichita, Kansas

Lease Name Dimond Well No. # 1

Location SE SW SW Sec. 8 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3680'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: C-G Drilling Company

Address: 107 Rule Bldg., Wichita, Kansas License No.

Operation Completed: Hour 3:15 AM Day 11th Month Sept. Year 1965

The Above well was plugged as follows:

326' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fluid was
up in the hole. 1st cementing plug and 1/2 sack of hulls was pushed in fluid
to 320', and cemented with 25 sacks, through the drill pipe. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged with hulls
on fluid at 40', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 9/13/65

INV. NO. 1992-W