

*W*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Sept. 16, 1966

RECEIVED  
THE KANSAS STATE CORPORATION COMMISSION  
SEP 19 1966  
CONSERVATION DIVISION  
Wichita, Kansas

9-19-66

Operator's Full Name Alpine oil & Royalty

Complete Address: 800 Bitting Bldg. Wichita, Kansas.

Lease Name Fisher Well No. #1

Location SW-NE-NE Sec. 8 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3585'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Glenn & Smith Pipe Pulling Co.

Address: 204 East 6 Ellinwood Kansas. License No. 396

Operation Completed: Hour 5:PM Day 16 Month Sept. Year 1966

The Above well was plugged as follows:

3577' of 5 1/2" pipe plugged back to 3500'. Perforation at 3330'. Sand to  
3300' & 5 sacks cement. 294' of 8 5/8" surface pipe circulated with 280  
sacks cement. Mud to 290', 10' rock bridge, 4 sacks cement with calcium  
per haler. Set for 2 1/2 hours. Baled down & 20 sacks cement. Hole filled  
with mud to 40', 10' rock bridge & 10 sacks cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 9/19/66  
INV. NO. 3943-W