

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 4 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Co.

Complete Address Box 308 Great Bend, Ks

Lease Name Schartz B Well No. 3

Location SW/SW/SW Sec. 20 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3723

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Co. Inc.

Address Box 364 Great Bend, Ks License No. 399

Operation Completed: Hour 10:30 AM Day 2 Month 11 Year 1970

The above well was plugged as follows:

340 ft of 8 5/8 surface pipe cemented with 250 sacks. 3717 ft of 5 1/2

long string cemented with 150 sacks. Top perf. 3508 ft. Sand back

to 3371 ft, 15 sacks cement with bailer. Pulled 1882 ft of 5 1/2.

Pumped 2 sacks hulls, 15 sacks gel. & 100 sacks cement to base of

cellar. Dowell Chemical Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 11/4/70

INV. NO. 2802-W