

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1966

CONSERVATION DIVISION
Wichita, Kansas

3-18-66

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: R. R. # 2, Great Bend, Kansas

Lease Name Pursel Well No. # 2

Location NE SW NE Sec. 20 Twp. 21 Rge. 13 (E) (W)

County Stafford Total Depth 3690'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 10:45AM Day 16th Month March Year 1966

The Above well was plugged as follows:

204' of 8 5/8" surface pipe, cemented with 175 sacks. 3696' of 5 1/2" long string
cemented with 100 sacks. Plug back T.D. 3663'. Top perferation 3476'. Pipe had
squeezed at 542' with 250 sacks of cement, no recovery of pipe. 25 sacks of
cement followed with 18 sacks of Gel-Mud displaced with 35 sacks of cement
with a total of 80 bbls. of water was pumped into the 5 1/2", bringing the bottom
cement with a top of 3200', and the top cement from 280' to the top of the 5 1/2"
2 sack of Gel-Mud and 40 sacks of cement was pumped, through the annulus of
of the braden head, to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

3/18/66

INV. NO.

2892-W

Signed:

Audie Elving
Well Plugging Supervisor