

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE-SW-NW

SEC. 2 TWP. 21 RGE. 13W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. _____ Lease Address - "D"

Operator M. B. Urmey, Co. Address 306 Insurance Bldg. Wichita-Kan

Field _____ County Stafford

Total Depth 3000 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 215 ft Circulated with cement.
5/8 casing set at 3537 ft - Plugged back from
bottom to 3392 with mud & Lane Well Plug - Filled with
Chert from 3392 ft to 3575 ft - Dumped 5 sacks of cement
at 3575 ft - Ripped off & Palled the 5/8 casing - Filled
with mud to 215 ft - Set Rock Bridge & 15 sacks of
Cement at 215 ft - Mud to 30 ft - Bridge & 10 sacks
of cement at the surface

C. M. Stough
District Conservation Agent

Date 11-8-49

PLUGGING
FILE SEC 2 TWP 21 RGE 13W
BOOK PAGE 182 LINE 38

11-10-49

RECEIVED
Conservation Div.
NOV 10 1949
STATE CORPORATION
COMMISSION
KANSAS