


15-145-01136-00000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 3 Twp. 23 Rge. (E) 17 (W)  
Location as "NE/CNW/KSWK" or footage from lines NW NW SW  
Lease Owner Colorado Oil Company  
Lease Name Hutchinson "F" Well No. 2  
Office Address 915 Union Natl. Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed January 25 1955  
Application for plugging filed March 4 1969  
Application for plugging approved March 4 1969  
Plugging commenced March 27 1969  
Plugging completed April 9 1969  
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production May 1963  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well XEK Leo Massey  
Producing formation Congl. Chert Depth to top 4152 Bottom Total Depth of Well 4276 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	246'	None
				5-1/2"	4275'	2618'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, ran sand to 4150' and dumped 5 sacks of cement.  
Rigged up on 5-1/2", put control head on, loaded hole.  
Shot pipe at 3140', 2913', 2602, worked pipe loose & pulled 83 joints. Allied pumped 20 sacks mud, 5 sacks hulls and 100 sacks of cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Co., Inc.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Bill K. Henrichs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs  
915 Union Natl. Bldg., Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of April 1969

My commission expires February 19, 1973

Betty J. McElwain  
Betty J. McElwain Notary Public.







WELL NO. 2

LEASE HUTCHINSON "F"

DRILL STEM TESTS

FORMATION TESTED	FROM	TO	TIME OPEN	RESULTS (BLOW, RECOVERY, BHP, FP)
Congl. Chert	4154	4163	25"	Gas to surface/2". Flowed oil/25" IFP 440#, FFP 720#. BHP 1280#/20".
Congl. Chert	4175	4195	60"	Very weak blow 60". Rec. 30' mud w/few spots stain. BHP 270#/60".

RECEIVED  
STATE CORPORATION COMMISSION

MAR 4 1969

CONSERVATION DIVISION  
Wichita, Kansas

SURVEYS (LOGS)

TYPE	COMPANY	DATE
Guard	Halliburton	1-17-55
Gamma Ray-Neutron	Halliburton	1-23-55

COMPLETION RECORD

Scout ticket information:  
 C.O. Perf. 56/4178-4190. No show  
 Sandfrac *w/ 6500 GAL oil and 7500 LB sand on 1-24-55*  
 Flow 45 BO/1 hr.  
 State Physical Productivity: 2-3-55. 484 BOFD/no wtr.  
 25/64" choke

**WELL RECORD - (CONTINUED)**

**ACIDIZING RECORD**

DATE				
QUANTITY (GALS.)				
MAX. TUB. PR.				
MAX. CAS'G PR.				
BLANKET				
HOURS				
METHOD				
OIL BEFORE				
OIL AFTER				
WATER BEFORE				
WATER AFTER				
DONE BY				

DEFLECTION			PLUGGING RECORD		
DEPTH	ANGLE	V. CORR.	START	FINISH	
			19	19	
GIVE RECORD OF PLUGS DRIVEN, CEMENT, ROCK, ETC., MUD AND HOW PLACED, AND ALL PIPE LEFT IN HOLE.					

**ADDITIONAL INFORMATION & RECOMMENDATIONS**