

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

Well Plugging Record  
K.A.R. -82-3-11Z  
**RECEIVED**

API NUMBER 15-185-23193-0000  
LEASE NAME Address Trust  
WELL NUMBER 1-2

TYPE OR PRINT  
NOTICE: Fill out completely and return to Cons. Div. office within 30 days.  
**AUG 21 2003**  
**KCC WICHITA**

800 Ft. from North Line of Section  
1980 Ft. from East Line of Section

LEASE OPERATOR Mull Drilling Co., Inc. SPOT LOCATION 140' S of S/2 Nw Ne  
ADDRESS P.O. Box 2758 Section 2 Township 21s Range 13w  
CITY, STATE, ZIP Wichita, Kansas 67201-2758 County Stafford  
PHONE # 316-264-6366  
Character of Well Dry and Abandoned  
Date Well Completed August 15, 2003  
Date Plugging Commenced August 15, 2003  
Date Plugging Completed August 15, 2003  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 14, 2003 (date)  
by Steve Middleton (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 3680

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	180			
Redbeds	Shale	180	282	8-5/8"	282	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Received plugging orders 08/14/03 from Steve Middleton. Plugged using total of 155 sx of 60/40 Poz, 6% Gel & 1/4#/sx Celloflake. Heavy mud in hole and between all plugs. Bottom plug @ 3515' with 30sx. 2nd plug at 730' with 50sx. 3rd plug at 310' with 50sx. Top plug at 40' with 10 sx cemented to surface. Plugged rathole with 10sx, no mousehole. Plug down at 6:00 am, 08/15/03. Allied ticket # 15971. Reported to KCC 08/15/03.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mull Drilling Co., Inc. (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott  
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 20th day of Aug., 2003



Pamela S. Fields  
(Notary Public)

My Commission Expires: \_\_\_\_\_

# Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

RECEIVED  
AUG 21 2003  
KCC WICHITA

## SAMPLE LOG

## Andress Trust 1-2

**LOCATION:** 140' S of S/2 Nw Ne Section 2 T 21s R 13w  
**API:** 15-185-23193-0000 Stafford County, Kansas

**OWNER:** Mull Drilling Co., Inc.  
**CONTRACTOR:** Sterling Drilling Company, Rig #1

**COMMENCED:** 04-Aug-03  
**COMPLETED:** 15-Aug-03

**TOTAL DEPTH:** **DRILLER** 3680 FEET  
**LOGGER** 3682 FEET

**Ground Elevation:** 1863  
**KB Elevation:** 1872

### LOG

0 -	3 FEET	Top Soil
3 -	24 FEET	Clay
24 -	50 FEET	Sand and Gravel
50 -	70 FEET	Clay
70 -	94 FEET	Sand and Gravel
94 -	135 FEET	Sand, Gravel and Clays
135 -	697 FEET	Redbeds
697 -	722 FEET	Anhydrite (Driller's)
722 -	1640 FEET	Shales and Salt
1640 -	3515 FEET	Limestone, Shale and Dolomite
3515 -	3680 FEET	Arbuckle

### CASING RECORDS

#### Surface Casing-8-5/8"

Spud at 6:00 pm on 08/04/03. Drilled 12-1/4" hole to 282'. Ran 6 joints of new 23# 8-5/8" surface casing, tally 287' set at 282' KB. Cemented with 250 sx 70/30 Poz, 3% CC, 2% Gel. Cement did circulate. Plug down at 10:30 pm on 08/04/03 by Allied. Ticket # 15963. Strapped bottom 3 joints, welded collars remaining 3 joints.

#### Plugging Data:

Received plugging orders 08/14/03 from Steve Middleton. Plugged using total of 155 sx of 60/40 Poz, 6% Gel & 1/4#/sx Celloflake. Heavy mud in hole and between all plugs. Bottom plug @ 3515' with 30sx. 2nd plug at 730' with 50sx. 3rd plug at 310' with 50sx. Top plug at 40' with 10 sx cemented to surface. Plugged rathole with 10sx, no mousehole. Plug down at 6:00 am, 08/15/03. Allied ticket # 15971. Reported to KCC 08/15/03.

### DEVIATION SURVEYS

3/4	degree(s) at	282	feet
3/4	degree(s) at	1710	feet
3/4	degree(s) at	3420	feet
1	degree(s) at	3525	feet
1-1/4	degree(s) at	3680	feet

RECEIVED

AUG 2 1 2003

KCC WICHITA

# Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

## SAMPLE LOG

## Andress Trust 1-2

<b>LOCATION:</b>	140' S of S/2 Nw Ne	Section	2	T	21s	R	13w
<b>API:</b>	15-185-23193-0000	Stafford County, Kansas					

**OWNER:** Mull Drilling Co., Inc.  
**CONTRACTOR:** Sterling Drilling Company, Rig #1

**COMMENCED:** 04-Aug-03  
**COMPLETED:** 15-Aug-03

<b>TOTAL DEPTH:</b>	<b>DRILLER</b>	3680	<b>FEET</b>
	<b>LOGGER</b>	3682	<b>FEET</b>

**Ground Elevation:** 1863  
**KB Elevation:** 1872

### LOG

0 -	3 FEET	Top Soil
3 -	24 FEET	Clay
24 -	50 FEET	Sand and Gravel
50 -	70 FEET	Clay
70 -	94 FEET	Sand and Gravel
94 -	135 FEET	Sand, Gravel and Clays
135 -	697 FEET	Redbeds
697 -	722 FEET	Anhydrite (Driller's)
722 -	1640 FEET	Shales and Salt
1640 -	3515 FEET	Limestone, Shale and Dolomite
3515 -	3680 FEET	Arbuckle

### CASING RECORDS

#### Surface Casing-8-5/8"

Spud at 6:00 pm on 08/04/03. Drilled 12-1/4" hole to 282'. Ran 6 joints of new 23# 8-5/8" surface casing, tally 287' set at 282' KB. Cemented with 250 sx 70/30 Poz, 3% CC, 2% Gel. Cement did circulate. Plug down at 10:30 pm on 08/04/03 by Allied. Ticket # 15963. Strapped bottom 3 joints, welded collars remaining 3 joints.

#### Plugging Data:

Received plugging orders 08/14/03 from Steve Middleton. Plugged using total of 155 sx of 60/40 Poz, 6% Gel & 1/4#/sx Celloflake. Heavy mud in hole and between all plugs. Bottom plug @ 3515' with 30sx. 2nd plug at 730' with 50sx. 3rd plug at 310' with 50sx. Top plug at 40' with 10 sx cemented to surface. Plugged rathole with 10sx, no mousehole. Plug down at 6:00 am, 08/15/03. Allied ticket # 15971. Reported to KCC 08/15/03.

### DEVIATION SURVEYS

3/4	degree(s) at	282	feet
3/4	degree(s) at	1710	feet
3/4	degree(s) at	3420	feet
1	degree(s) at	3525	feet
1-1/4	degree(s) at	3680	feet