

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15.185.01698.0000

LEASE NAME REED

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER #3

3630' Ft. from S Section Line

4950' Ft. from E Section Line

SEC. 8 TWP. 21 RGE. 13 (E) or (W)

COUNTY STAFFORD

Date Well Completed 7-23-51

Plugging Commenced 4-25-90

Plugging Completed 4-25-90

LEASE OPERATOR WHITEHAWK OIL COMPANY

ADDRESS BOX 3366 Tulsa, OK 74101

PHONE#(316) 792-4309 OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-25-90 (date)

by Daune Rankin (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Lansing-Arbuckle Depth to Top 3440 Bottom 3609 T.D. 3625'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	325'	0'
				5 1/2"	3625'	2830'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
4 sxs hulls, 10sx gel, 50sx cement, 10 sx gel, 1 sx hull, 100 sx cement

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Steve Mitchell License No. \_\_\_\_\_

Address 2611 27th 1-17 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: \_\_\_\_\_

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

X (Signature) R Taylor  
 (Address) Box 3363 Tulsa OKLA 74101

SUBSCRIBED AND SWORN TO before me this 6<sup>th</sup> day of July, 1990

X Daune E. Rankin  
 Notary Public

My Commission Expires: 11-21-93

RECORDED  
 STATE OF KANSAS  
 JUL - 9 1990  
 CONSERVATION DIVISION  
 Wichita, Kansas

COMPANY: Westgate-Greenland Oil Company  
 CONTRACTOR: Jackson Drilling Corporation  
 FARM: Reed #3  
 LOCATION: NW SW NW Sec. 8-21-13W, Stafford County, Kansas  
 COMMENCED: July 8, 1951  
 COMPLETED: July 20, 1951- Rotary  
 July 23, 1951- Cardwell  
 ELEVATION: 1906 DF

0	to	85	Sand
85	to	123	Shale and pyrite
123	to	127	Pyrite
127	to	131	Iron and sand
131	to	165	Shale
165	to	240	Hard sand
240	to	325	Shale and shells
325	to	782	Shale, shells and Red bed
782	to	807	Anhydrite
807	to	1080	Shale and shells
1080	to	1530	Shale and shells w/salt
1530	to	1590	Shale and shells
1590	to	1660	Lime w/shale breaks
1660	to	1755	Lime and shale
1755	to	2190	Lime
2190	to	2410	Shale and Lime
2410	to	2625	Shale w/lime
2625	to	2825	Shale and lime
2825	to	2875	Lime w/shale
2875	to	3070	Lime and shale
3070	to	3110	Lime
3110	to	3290	Lime w/shale
3290	to	3307	Shale
3307	to	3319	Brown lime
3319	to	3355	Lansing lime
3355	to	3540	Lime
3540	to	3590	Shale and lime
3590	to	3625	Arbuckle
		3625	T. D.

Set 325 feet 8 5/8"-36" Surface pipe. Cemented with 225 sacks cement and 3 sacks calcium chloride.

Set 5 1/2" 14# casing at 3625. Cemented with 75 sacks cement.

Perf. 48 holes 3590-3609, swabbed 90 BO in 5 hours. No. acid

Tops: Anh-782; Heeb-3185; Brown Lime-3305; Lansing 3316; Simpson 3558; Arbuckle 3588. (DF)

Potential: 553 Bbls. - No water.

Filed 25 BOPD Affidavit as of July 24, 1951

**CERTIFICATE**

I, G. E. Bitler, do hereby certify that the above and foregoing is a true and correct copy of log of the Reed #3, Section 8-21-13W, Stafford County, Kansas, as reflected by files of the Westgate-Greenland Oil Company.

RECEIVED  
 STATE CORP. DIV.  
 MAR 29 1953  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

*G. E. Bitler*  
 G. E. Bitler

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 3rd day of August, 1951.

*Esther L. Ladd*  
 Notary Public

My commission expires May 25, 1953.