


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bifling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Stafford County. Sec. 8 Twp. 21 Rge. 13W (E/W/W)
Location as "NE/CNW/SW" or footage from lines SE SW SE
Lease Owner George F. Johnston
Lease Name C. H. Harter Well No. 1-B
Office Address 304 Orpheum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Nov. 13, 19 48
Application for plugging filed Nov. 13, (verbal) 19 48
Application for plugging approved Nov. 15, 19 48
Plugging commenced Nov. 13, 19 48
Plugging completed Nov. 14, 19 48
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3706 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Surface pipe 8-5/8" - 480 feet - Circulated with cement. Hole full of heavy mud. Set plug and 15 sacks of cement at 200 feet through the drill pipe. Mud to 30 feet. Plug and 10 sacks of cement at the surface. This well was drilled 25 feet from Well #1. Lost hole that was plugged on the 28th of October, 1948.

RECEIVED
STATE CORPORATION COMMISSION
KANSAS
JAN 10 1949
1-10-49

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Brunson Drilling Co., Inc.,
Address 302 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.
George F. Johnston Jr. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George F. Johnston Jr.
(Address) Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 7th day of January, 1949.
Notary Public.

My commission expires Feb 28, 1952

22-5133-s 9-48-10M
PLUGGING
FILE SEC 8 T 21 R 13W
BOOK PAGE 68 LINE 20

C. H. Harter #1A

SE SW SE Sec. 8-21-13W
Stafford County, Kansas

Commenced RD: 10/19/48
Completed RD: 11/13/48
Total Depth : 3706'

Elevation: 1906
Initial Prod: Dry
Contractor: Brunson Drilling Co., Inc.

Casing 480' - 8 5/8"

STRATA	DEPTH
Sand & shells	72
Pyrite	140
Shale & shells	240
Sandy shale	295
Shale & shells	400
Redbed & shells	795
Anhydrite	825
Shale & shells	1150
Silt & shells	1360
Shale & shells	1450
Shale & lime	1690
Lime & shale	2020
Lime	2260
Shale & lime	3035
Lime	3211
Shale & lime	3365
Lime	3675
Shale	3706
Total Depth	3706

We hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

BRUNSON DRILLING CO., Inc.
By

H. D. Brunson
H. D. Brunson President

DEC 20 1948

Signed and sworn to in my presence this 23rd day of November, 1948, by H. D. Brunson, President of the BRUNSON DRILLING COMPANY, INC., a corporation in the State of Kansas.

PLUGGING
 FILE SEC 8 T 21 R 13W
 My commission expires 12/2 1952
 BOOK PAGE 67 LINE 20

Ralph B. McLaughlin
Notary Public