


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 West 10th Building  
Wichita, Kansas

Stafford County, Sec. 8 Twp. 21 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW SW  
Lease Owner Greenland Drilling Co., et al  
Lease Name Dimond Well No. 1  
Office Address 506 Union National Bank Bldg.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 8-24-53 19\_\_  
Application for plugging filed 8-23-53 19\_\_  
Application for plugging approved 8-23-53 19\_\_  
Plugging commenced 8-24-53 19\_\_  
Plugging completed 8-24-53 19\_\_  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3650 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	203	8 5/8	203'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole full of heavy rotary mud - set plug @ 200' w/20 sks. cement  
Mud to 35' RBM - plug & 10 sks cement at surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Greenland Drlg. Co.  
Address Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Richard S. Davis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Richard S. Davis*  
506 Union Nat'l. Bank Bldg. Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 19 53

My commission expires July 8, 1957

*Mary Ellen Cummings* Notary Public.

PLUGGING  
FILE SEC 8 T 21 R 13W  
BOOK PAGE 124 LINE 33

24-7866-5 3-53-20M  
**RECEIVED**  
STATE CORPORATION COMMISSION  
SEP - 3 1953  
CONSERVATION DIVISION  
Wichita, Kansas

WELL LOG

Company: Greenland Drilling Co., et al  
 Farm: Diamond #1  
 Total depth: 3650'  
 Conn: 8-13-53  
 Comp: 8-21-53  
 Casing: 203' of 8 5/8"

Sec. 8 T. 21S R. 13W  
 Loc. NE NW SW  
 County: Stafford  
 Elev: 1917 R.O.B.  
 Production: D & A

## Figures Indicate Bottom of Formations


125	Sand & clay	<u>Tons</u>	
300	Shale & Shells	Anhydrite	805
395	Shale & Sand	Ft. Riley	1705
805	Red Bed	Feb.	3216
818	Anhydrite	Brown Lime	3395
1510	Shale & Shells	Lansing	3318
1610	Shale, Shells w/Salt	Arb.	3612
1735	Sdy. Lime w/Sh. Brks.		
1900	Lime & Shale		
2010	Lime w/Shale Brks.	DST 3190 - 3505'	
3108	Lime & Shale	Open 20 min. weak 5' blow	
3160	Lime	BIMP 1860'	
3202	Lime & Shale	Recovery 5' max	
3206	Shale		
3260	Lime & Shale	DST 3612 - 3650'	
3313	Sdy. Shale & Lime	1180' BIMP	
3339	Sdy. Shale	Recovery 210' max	
3580	Lime		
3620	Shale & Lime w/Chert		
3612	Shale & Lime		
3650	Arb. Lime		
3650	T.D.		

State of Kansas ( )  
 County of Sedgwick) ss.

I, Richard S. Davis of the Greenland Drilling Company upon oath state that the above and foregoing is a true and correct copy of the log of the Diamond #1 well.

  
 Richard S. Davis

Subscribed and sworn to before me this 31st day of August, 1953.

  
 Notary Public

My Commission Expires: July 8, 1957.

