


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

STAFFORD County, Sec. 8 Twp. 21 Rge. 13 (X) W (W)

Location as "NE/CNW/SW" or footage from lines NE SW NE
Lease Owner PETROLEUM INC.
Lease Name FISCHER "A" Well No. 2
Office Address Route 2, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 31 19 56
Application for plugging filed December 31 19 56
Application for plugging approved December 31 19 56
Plugging commenced December 30 19 56
Plugging completed December 31 19 56
Reason for abandonment of well or producing formation
No Producing Zones
If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well R. M. Brundege, Box 283, Hoisington, Kansas
Producing formation ----- Depth to top --- Bottom --- Total Depth of Well 3617' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud up with heavy mud to 180', pushed down 1/3 sack hulls to 180' followed by wooden plug. Placed 20 sacks cement through drill pipe on to plug. Mud up to 35' and place 1/3 sack hulls at 35' followed by wooden plug and 10 sacks cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address Route 2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (~~licensed operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
Route 2, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of January, 19 57

My commission expires July 11, 1960

[Signature]
RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

PLUGGING
FILE SEC 8 T. 21 R. 13 W
BOOK PAGE 130 LINE 32

JAN 10 1957 1-10-57
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

15.185.11705.0000

COMPANY PETROLEUM, INCORPORATED

SEC. 8 T. 21S. R. 13W

FARM FISCHER 'A' NO. 2

LOC. NE, SW, NE

TOTAL DEPTH 3617'

COUNTY Stafford Co., Kansas

COMM. ~~XXXXXX~~ Dec. 19, 1956 EMP. December 31, 1956

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 210' W/175 sax.

ELEVATION 1899' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

105	Clay & sand	Anhydrite	785
165	Hard sand	Heebner	3179
210	Shale	Toronto	3200
785	Sand & shale	Douglas	3216
800	Anhydrite	B. Lime	3302
1300	Red bed & shale	Kansas City	3314
2355	Shale & lime	Arbuckle	3570
2840	Shale & shells		
2985	Lime & shale		
3199	Lime		
3310	Lime & shale		
3617	Lime		
3617	T. D.		

State of KANSAS

County of BARTON

PLUGGING
 FILE SEC. 8 T. 21 R. 13W
 BOOK PAGE 130 LINE 32

I, Verne A. Morris

of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #2 Fischer 'A' well

Verne A. Morris

Subscribed and sworn to before me this 8th day of January, 1957

STATE CORPORATION COMMISSION

My Commission Expires: July 11, 1960

Ed J. Brown
NOTARY PUBLIC