

All Information Completely
Required Affidavit
or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 8 Twp. 21 S Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW NE NE

Lease Owner ALPINE OIL & ROYALTY CO., INC.

Lease Name Eric Fischer Well No. 1

Office Address 800 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil well

Date well completed May 20 1965

Application for plugging filed September 7 1966

Application for plugging approved September 7, 1966

Plugging commenced September 13, 1966

Plugging completed September 16, 1966

Reason for abandonment of well or producing formation non-productive in commercial quantities

If a producing well is abandoned, date of last production September 9 1966

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman Justice

Producing formation Arbuckle Depth to top 3574 Bottom Total Depth of Well 3589 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	294'	Cemented
				5 1/2"	3577'	2669 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with sand from 3500 feet to 3300 feet. Ran 5 sacks of cement from 3300 feet to 3260 feet. Set plug at 290 feet. Rock bridge from 290 feet to 280 feet. Ran 5 sacks of cement. Let set for 3 hours, bailed out water and ran 20 sacks of cement from 280 feet to 150 feet. Mudded from 150 feet to 40 feet. Rock and 10 sacks of cement from 40 feet to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1966
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Glenn and Smith Pipe Pulling Company
Address Box 156, Ellinwood, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dwight J. Wilson
800 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 1966

My commission expires August 10, 1969

Virginia Mundell
Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

FISCHER #1
SW NE NE SECTION 8-21S-13W
STAFFORD COUNTY, KANSAS

COMMENCED: MAY 7, 1965
COMPLETED: MAY 15, 1965

OPERATOR - ALPINE OIL & ROYALTY Co., INC.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	120	SAND	
120	130	HARD SAND	
130	255	SHALE AND SHELLS	
255	275	SAND AND SHALE	
275	294	SHALE AND SHELLS	RAN 7 JOINTS 8-5/8" CASING, SET @ 294' w/280 SX. CEMENT
294	855	RED BED AND SHALE	
855	970	ANHYDRITE, SHALE, SHELLS	
970	1590	SHALE AND SHELLS	
1590	1795	SHALE AND LIME	
1795	2085	LIME	
2085	2320	SHALE AND LIME	
2320	2515	SHALE AND SHELLS	
2515	3115	SHALE AND LIME	
3115	3190	LIME	
3190	3330	SHALE AND LIME	
3330	3370	LIME	
3370	3410	SHALE, LIME, CHERT	
3410	3520	LIME	
3520	3570	LIME AND SHALE	
3570	3585	LIME	
3585	TD		RAN 5 1/2" CASING TO 3577', CEMENTED w/150 SX. CEMENT

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE SW NE NE SECTION 8-21S-13W, STAFFORD COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 18TH DAY OF MAY, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968.

RECEIVED
STATE CORPORATION COMMISSION

SEP 7 1966

CONSERVATION DIVISION
Wichita, Kansas