

15185-19492.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Fisher

WELL NUMBER "A" #3

SPOT LOCATION S/2-SE NE

SEC. 8 TWP. 21 RGE 13 (E) or (W) _____

COUNTY Stafford

Date Well Completed 9-12-63

Plugging Commenced 3-14-85

Plugging Completed 3-21-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Four-Way Operating, Inc.

ADDRESS Box 698, Great Bend, Ks. 67530

PHONE # 792-2506 OPERATORS LICENSE NO. 5310

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 3614'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	329'	None
				4-1/2"	3612'	2,014.12'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 3500' and 4 sacks of cement. Shot casing at 3200'. Shot casing at 2500' and 2000'. Pulled 63 joints of 4-1/2" casing. Squeezed well with 2 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 150 sacks 60/40 pozmix cement with 4% added gel and 3% calcium chloride. Maximum pressure was 400 psi and shutin 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss. _____

James W. Rockhold (employee of operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 27th day of March, 1985

STATE NOTARY PUBLIC
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

My Commission expires: _____

Iona M. Leatherman
Notary Public

WELL LOG

15.185.19492-0000

COMPANY Petroleum Inc

SEC. 8 T. 21S R. 13W

FARM Fischer

NO. A-3

LOC. S $\frac{1}{2}$ SE NE

TOTAL DEPTH 3614'

COUNTY Stafford

COMM. 4-13-63

COMP. 4-22-63

CONTRACTOR Garvey Drilling Company

CASING 10 3/4" @ 329' w/450 sx

4 1/2" @ 3612' w/120 sx

ELEVATION 1898' DF

PRODUCTION Conglomerate Sand

FIGURES INDICATE BOTTOM OF FORMATIONS

- 90' Surface Soil and Sand
- 145' Hard Sand
- 160' Shale
- 695' Shale, Shells, and Red Bed
- 1570' Shale and Shells
- 1765' Shale and Lime
- 1950' Lime and Shale
- 2115' Lime
- 2280' Lime and Shale
- 3055' Shale and Lime
- x8
- 3210' Lime
- 3305' Shale and Lime
- 3614' Lime
- 3614' RTD

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1965

CONSERVATION DIVISION
Topeka, Kansas

State of Kansas

County of Barton } ss

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Fischer A-3 well.

Sam N. Stephens

Subscribed and sworn to before me this 25th day of April 19 63

My Commission Expires: April 14th, 1967

Arthur J. Miles
NOTARY PUBLIC