

15.185.01695.0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

Drilling Completed  
API NUMBER 12-31-52

LEASE NAME Reed "B"

WELL NUMBER 3

SPOT LOCATION 330'S - 990'W

SEC. 8 TWP. 21 SRGE. 13 (W)

COUNTY Stafford

DATE WELL COMPLETED 12-31-52

PLUGGING COMMENCED 11-25-83

PLUGGING COMPLETED 12-6-83

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Cities Service Oil & Gas Corporation

ADDRESS 800 Sutton Place, Wichita, Ks. 67202

PHONE #(316) 265-5624 OPERATORS LICENSE NO. 5447

CHARACTER OF WELL Oil  
(OIL) GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? District #1  
Well Completed

Is ACC-1 FILED? 12-31-52 IF NOT, IS WELL LOG ATTACHED? Well log attached

PRODUCING FORMATION LSG - KC DEPTH TO TOP 3393' BOTTOM 3489' T.D. 3586'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

#116.55

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	360'	- 0 -
				7"	3580'	1890'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Pulled rods and tubing. Dumped sand to 3250 ft. Dumped 7 sacks of cement at 3250 ft. Stretched and cut 7" casing at 2000 ft. Pulled 60 joints (1890 ft.) 7" casing. Pumped 4 sacks hulls, 30 sacks gel, 220 sacks 60/40 Pozmix down 10 3/4" casing. Plug and abandonment completed December 6, 1983.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Clarke Corporation LICENSE No. \_\_\_\_\_  
ADDRESS 107 W. Fowler-

Medicine Lodge, Ks. 67104

STATE OF Kansas COUNTY OF Sedgwick, ss.


Charles N. Richmond (EMPLOYEE OF OPERATOR) OR  
~~NOTARY PUBLIC~~ OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT  
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND  
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND  
CORRECT, SO HELP ME GOD.

(SIGNATURE) Charles N. Richmond  
Charles N. Richmond  
(ADDRESS) 800 Sutton Place, Wichita, Ks.  
67202

SUBSCRIBED AND SWORN TO BEFORE ME THIS 19 DAY OF December, 1983

Jacqueline Pierce  
NOTARY PUBLIC  
Jacqueline Pierce

MY COMMISSION EXPIRES: 2-27-85



WELL RECORD 15.185.01695.0000

Lease Reed "B" Well No. 3 S. 8 T. 21 R. 13W  
 County Stafford State Kansas Elev. 1909 (1907 Gr)  
 Location 330' South and 990' West of N/4 Cor.  
 Dr. Commenced Dec. 10, 1952 Dr. Completed Dec. 31, 1952  
 Drilled By Holm Drilling Company T. D. 3586'  
 Acid 2000 gals. Lsg.-K. C. P.B.T.D. 3560'  
 Initial Prod. BHP Gauge: 1483 oil, 62 water, 24 hrs. (1-16-53)

Casing Record

10-3/4" @ 360' cem. 300 sx cement  
 7" @ 3580' cem. 150 sx cement

Corr. Heebner 3186'  
 Corr. Brown Ls. 3305'  
 Corr. Lansing 3317'  
 Corr. Congl. 3559'  
 Corr. Simpson Sh. 3570'  
 Corr. Arbuckle 3578'  
 Penetration 8'  
 Total Depth 3586'

Fillup: 207' oil in 55 mins.  
 410' oil in 2 hrs. 15 mins.  
 661' oil in 19 hrs. 40 mins.

1-1-53 Pumped 87 oil, no water, 8 hrs.

Set Lane-Wells plug at 3561; 1 1/2 gals. rock on plug;  
 PBTD 3560 SLM.

Perf. 40 shots 3457-70; 1560' fluid in 1 hr. 55 mins.  
 2345' fluid in 4 hrs. 35 mins.  
 Hole full oil in 20 hrs. 25 mins.

1-5-53 Pumped 207 oil, no water, 15 hrs.

Perf. 48 shots 3436-49.

1-7-53 Az. 1000 gals. 3457-70  
 " Az. 1000 gals. 3436-49

(Over)

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 31 1953

Geol. 16A  
 3-48

CONSERVATION DIVISION  
 Wichita, Kansas