

15-009-30084-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Schreiner Petroleum
Complete Address: 910 Central Bldg., Wichita, Kansas
Lease Name Dolecheck Well No. # 1
Location SW SE NE Sec. 26 Twp. 16 Rge. 12 (E) (W) W
County Barton Total Depth 3346
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling Company
Address: Box 405, Chase, Kansas License No. 436
Operation Completed: Hour 11 A.M Day 24 Month 8 Year 1965

The Above well was plugged as follows:

8 5/8" 324' Cwc.
sanded hole back to 3320' & dumped 5 sax cement with dump bailer.
Pulled pipe. Mudded hole to 320'; set rock bridge; displaced 25 sax
cement. Mud to 40'; set rock bridge & displaced 10 sax cement, cement-
ing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Truman
Well Plugging Supervisor

DATE 8/27/65
INV. NO. 1702-W