

15.185.01857.0000

Form CP-3
Rev. 6-26-62

NO
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 3 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name H. Hullman Well No. # 2

Location C NE NW SW Sec. 7 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3737'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 12:15PM Day 2nd Month Feb. Year 1966

The Above well was plugged as follows:

906' of 8 5/8" surface pipe, cemented with 365 sacks. 3734' of 5 1/2" long
string, cemented with 50 sacks. This is an open hole. Bottom of the hole
was sanded to 3400', and cemented with 5 sacks. 2202' of 5 1/2" long string
was recovered from the hole. Hole was filled with mud to 300', rock bridge
from 300' to 290', and cemented with 25 sacks. Hole was filled with mud
to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base
of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/3/66

INV. NO. 2682-11