

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW NE SW , Sec. 7 , T 21 S, R 14 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185 21,301

_____ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

_____ feet from W/E section line

Operator License # 5230

Lease Name Schartz "B" Well # 1

Operator: Petroleum Energy, Inc.
Name & Suite 415, First Nat'l Bank Bldg.
Address 105 N. Main Street
Wichita, KS 67202

County Stafford

Well Total Depth 3760 feet 122.20

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 914

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:00 am Day: 13 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO James Ray

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2 set at 3726 Perfs 3585-96 PBTB 3700

1st plug sanded back to 3520 and dumped 5 sx cement on top of sand.

2nd plug squeezed through head with 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel,

1 sack hulls and released 8 5/8" rubber plug and pumped an additional 100 sx cement.

Maximum pressure 1000# and shut-in pressure 500#.

Signed Steve Demont
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:45 am Day: 13 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 3725 Perfs 3585-96 PBTB 3700'

1st plug sanded back to 3520 and dumped 5 sx cement on top of sand.

2nd plug squeezed through head with 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel,

1 sack hulls and released 8 5/8" rubber plug and pumped an additional 100 sx

cement. Maximum pressure 1000# and shut-in pressure 500#

Remarks: Use 60/40 Pozmix with 2% gel 3% cc. by Allied. They recovered 1700' 5 1/2"
production casing.

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

Signed Steve Demont
(TECHNICIAN)

INVOICED
DATE 2-22-84
INV. NO. 0399