

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Great Bend Pipe & Supply Co., Inc.Complete Address: Drawer "B", Great Bend, KansasLease Name Frey Well No. # 3Location SW NW NE Sec. 7 Twp. 21 Rge. 14 (E) (W) WCounty Stafford Total Depth 3722Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Knight Casing Pulling Co.Address: Box 304, Chase, Kansas License No. 436Operation Completed: Hour 4:00PM Day 21st Month March Year 1964

The Above well was plugged as follows:

883' of 8 5/8" surface pipe, cement circulated. 3720' of 5 1/2" long
string, cemented with 75 sacks. Bottom of hole was sanded to 3700',
and cemented with 5 sacks. Hole was filled with mud to 300', with
10' rock bridge, and cemented with 25 sacks. Hole was filled with
mud to 40', with 10' rock bridge, and cemented with 10 sacks to base
of cellar.

3248' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICEDDATE 3/26/64INV. NO. 8850-WSigned: Archie Elving
Well Plugging Supervisor