

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-193-20274-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 36-10S-31W  
4950 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: WIEGEL Well #: 61-36  
County: THOMAS Total Vertical Depth: 4671 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 S ST FRANCIS PO BOX 2757  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4671		325 SX
SURF	8.625	349		130 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/18/2017 9:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: SEAN FRIES Company: GORE OIL COMPANY Phone: (308) 340-2773

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/650 # hulls.  
8 5/8" surface casing set at 349' w/230 sx cement.  
4 1/2" production casing set at 4667' w/325 sx cement.  
TOC 3310', TD 4671', PBD 4604'.  
Port Collar set at 2457' w/575 sx cement.  
Perforations: 4410' - 4418', 4188' - 4192', 4130' - 4136', 4103' - 4106', 4085' - 4090', 4030' - 4038' and 3955' - 3960'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/18/2017 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 3954' and pumped 100 sx cement w/400 # hulls. Pulled tubing to 2917' and pumped 95 sx cement w/150 # hulls. Pulled tubing to 1441' and pumped 120 sx cement w/100 # hulls. Circulation hose on vacuum. No returns. Pulled tubing to 624' and pumped 100 sx cement. Cement to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 15 sx cement. Casing standing full of cement. Connected to 8 5/8" surface casing and pumped 20 sx cement. Pressured to 300 psi.

GPS: 39.14690N -100.72704W

Perfs:

Top	Bot	Thru	Comments
4410	4418		
4188	4192		
4103	4136		
4090	4094		
4085	4089		
4030	4038		
3955	3960		

INVOICED  
AUG 31 2017

KCC WICHITA  
AUG 24 2017  
RECEIVED

Remarks: SWIFT SERVICES INC. TICKET # 30,439 PROBABLE CASING LEAK.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

AUG 03 2017