

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-20746-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 17-25S-5W  
330 feet from N Section Line, 990 feet from W Section Line  
Lease Name: GEFFERT Well #: 1  
County: RENO Total Vertical Depth: 3532 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3532	1774	180 SX
SURF	8.625	328		225 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/12/2017 12:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY Company: HERMAN LOEB Phone: (316) 215-1873

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/14/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3374' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 1774' PULLED CASING. RAN TUBING TO 750' SPOTTED 50 SX CEMENT, WAITED 2 HOURS TAGGED CEMENT @ 612', PULLED TUBING TO 375' CIRCULATED TO SURFACE WITH 185 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3424	3432		

Remarks: TICKET #53355 - QUES - EL DORADO

Plugged through: TBG

INVOICED  
AUG 31 2017

District: 02

Signed \_\_\_\_\_

*B. J. Hope*

(TECHNICIAN)

*1/3c*