

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-19437-00-00

Spot: SENWSWNW

Sec/Twnshp/Rge: 5-35S-13E

3617 feet from S Section Line, 4700 feet from E Section Line

Lease Name: J R HYDER-STEINBERGER U Well #: 10

County: CHAUTAUQUA

Total Vertical Depth: 750 feet

Operator License No.: 32255

Op Name: KANSAS ENERGY COMPANY, L.L.C.

Address: BOX 68

SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6	750		0 SX
SURF	10	40		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/28/2017 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: P.J. BUCK

Company:

Phone: (620) 725-3636

Proposed
Plugging
Method:

Surface cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Spot 50' plug of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS

Witness Type: NONE

Date/Time Plugging Completed: 06/29/2017 10:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 660' gelled hole and spotted 20 sack plug. Pulled 1" and perforated tubing at 400'. Hooked onto tubing and pulled into at 30'. Ran down backside of tubing to 400' and spotted 20 sack plug. Pulled up to 275'. Ran 1" down inside of tubing to 275'. Circulated cement to surface in both strings of 1" on backside and inside of tubing. Pulled both strings of 1" and topped well off. A total of 200 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
700	710		

RECEIVED
KCC DIST # 3
AUG 22 2017
CHANUTE, KS

DS

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY THE OPERATOR WITH THE KCC **INVOICED**

Plugged through: TBG

AUG 31 2017

District: 03

Signed DS

(TECHNICIAN)