

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-19441-00-00
Spot: SWSNWNW Sec/Twnshp/Rge: 5-35S-13E
4237 feet from S Section Line, 4294 feet from E Section Line
Lease Name: JR HYDER-STEINBERGER U Well #: 14
County: CHAUTAUQUA Total Vertical Depth: 750 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6	750		0 SX
SURF	10	40		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Spot 50' plug of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2017 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 680' gelled hole and spotted 20 sack plug. Pulled 1" and perforated the 5 1/2" casing at 450' and 275'. Ran 1" back into 450' and spotted 20 sack plug. Pulled up to 275' and circulated cement to surface with 100 sacks of cement. Pulled 1" and topped well off. A total of 140 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
700	710		

RECEIVED
KCC DIST # 3
AUG 22 2017
CHANUTE, KS
DS

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR WITH THE KCC **VOICED**

Plugged through: TBG

AUG 31 2017

District: 03

Signed _____

(TECHNICIAN)