

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-22073-00-02
Spot: E2E2SENE Sec/Twship/Rge: 26-31S-33W
3300 feet from S Section Line, 280 feet from E Section Line
Lease Name: PRINTZ FARMS Well #: 5H-26-31-33
County: SEWARD Total Vertical Depth: 6002 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL ROAD, SUITE 1200
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4900		WITH 2 SX CMT
PROD	4.5	5983	1916	WITH 300 SX CMT
SURF	8.625	1692		WITH 725 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/16/2017 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Recvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4900' WITH 2 SX CMT. PLUG AT 1720' WITH 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2017 12:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:


Actual Plugging Report	Perfs								
SET CIBP @ 4900' WITH 2 SX CMT. 1ST PLUG AT 1720' WITH 50 SX CMT. 2ND PLUG AT 540' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.	<table border="1"><thead><tr><th>Top</th><th>Bot</th><th>Thru</th><th>Comments</th></tr></thead><tbody><tr><td>4950</td><td>4956</td><td></td><td></td></tr></tbody></table>	Top	Bot	Thru	Comments	4950	4956		
Top	Bot	Thru	Comments						
4950	4956								

Remarks: **COMPLIANCE ISSUE: DENIED TA S1 10 YRS** USED COMMON CEMENT BY ORR.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

INVOICED

AUG 31 2017

RECEIVED
AUG 18 2017
KCC DODGE CITY