

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-00772-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 9-30S-8W
990 feet from N Section Line, 2310 feet from E Section Line
Lease Name: EVANS Well #: 2
County: KINGMAN Total Vertical Depth: 4340 feet

Operator License No.: 3067
Op Name: MOLITOR OIL, INC.
Address: 3885 SW 110 ST
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4332	2805	250 SX
SURF	8.625	247		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/15/2017 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-6964

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 06/20/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

SAND TO 4150', BAILED 5 SACKS CEMENT ON SAND, SET CIBP @3785', BAILED 2 SX CEMENT ON TOP. CUT CASING FREE AT 2805', PULLED CASING TO 1300', PUMPED 10 SACKS CEMENT, PULLED CASING TO 800', WAITED 2 HRS, TAGGED CEMENT AT 1050' PUMPED 35 SACKS CEMENT AT 800', PULLED CASING 288', CIRCULATED CEMENT TO SURFACE WITH 120 SACKS CEMENT. CEMENT FELL 15' FILLED WITH 7 SX CEMENT.


Remarks: QUAITY WELL PROVIDED CEMENT FOR THIS JOB

Plugged through: CSG

INVOICED
AUG 31 2017

District: 02

Signed



(TECHNICIAN)

1/4