

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-23195-00-00  
Spot: SESESW Sec/Twnshp/Rge: 24-14S-15W  
330 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: RICHARD KILIAN Well #: 2  
County: RUSSELL Total Vertical Depth: 3185 feet

Operator License No.: 3134  
Op Name: MORRIS, TERRY E. DBA G L M COMPA  
Address: PO BOX 193  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3184	2017	150 SX
SURF	8.625	398	0	225 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/13/2017 8:30 AM  
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.  
Proposal Rcvd. from: TODD L. DINKEL Company: MORRIS, TERRY E. DBA G L M CO Phone: (785) 639-5415

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Left 30 joints of tubing and packer at bottom of well.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/13/2017 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

06/05/2017- Parted tubing 30 joints above packer. Ran in with over shot and hit bad casing. The 5 1/2" casing had parted and shifted. Could not get down. Ran tapered mills and flat bottom mills and got outside of casing. Tried 2" tubing, then 1" tubing and could not get past bad casing. Pulled 445' of 5 1/2" casing out. Ran a 7" flat bottom mill to clean top of the casing. Ran 5 1/2" casing back in with 7" overshot skirt over the 5 1/2" casing. Ran in mills and got down a little deeper but casing was curling inside itself. Ran in with 1" tubing and stacked out at about 575'. (Worked 5/days a week 10 to 12 hours per day)  
07/13/2017- Hooked to 1" tubing at 550' and pumped 115 sx cement. Circulated cement out of 5 1/2" casing. Pulled 1" tubing out and hooked to 5 1/2" casing. Pumped 75 sx cement and circulated out 8 5/8" surface casing. Hooked to 8 5/8" surface casing and pumped 55 sx cement at 250 psi. Shut in pressure 200 psi.

GPS: 38.81379 -098.93422

Perfs:

Top	Bot	Thru	Comments
3149	3152		
3042	3044		
3027	3029		
3017	3019		
2982	2984		

KCC WICHITA  
AUG 24 2017  
RECEIVED

INVOICED  
AUG 31 2017

Remarks: GLOBAL CEMENTING TICKET # 3030

Plugged through: TBG

District: 04

Signed Ray Dinkel

(TECHNICIAN)

C M

JUL 18 2017