

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-00811-00-00  
Spot: NENESW Sec/Twnshp/Rge: 15-30S-8W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: LATTIMORE GAS UNIT Well #: 1  
County: KINGMAN Total Vertical Depth: 4270 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 S MAIN STE 505  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4270		100 SX
SURF	8.625	200		135 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/15/2017 8:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY Company: PICKRELL DRILLING CO Phone: (620) 793-2316

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/15/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 4120' CAPPED WITH 2 SX CEMENT ON TOP. RAN BOND LOG, CEMENT UP HIGH, BUT RATTY, NOT ABLE TO PULL CASING. PERF CASING @ 1250' LOADED CASING WITH GEL-SPOTTED 40 SX CLASS A CEMENT 3% CC, THRU TUBING, TAGGED @ 900'. PERF CASING @ 775' SPOTTED 35 SX CEMENT THRU TUBING. PERF CASING @ 250' CIRCULATED TO SURFACE WITH 20 SX CEMENT. CUT HEAD OFF AND ONE INCHED TUBING TO 155' AND FILLED BETWEEN THE 4.5" AND 8 5/8" WITH 40 SX CEMENT ON 6/15/17.

Perfs:

Top	Bot	Thru	Comments
4193	4204		
4176	4180		

INVOICED  
SEP 01 2017

Remarks: BASIC ENERGY PROVIDED CEMENT FOR THIS JOB.

Plugged through: TBG

District: 02

Signed [Signature] DISTRICT SUPERVISOR  
(TECHNICIAN)