

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-109-20767-00-00  
Spot: SWNWNENE Sec/Twnshp/Rge: 33-12S-34W  
648 feet from N Section Line, 1318 feet from E Section Line  
Lease Name: KYLE HEMMERT Well #: 1  
County: LOGAN Total Vertical Depth: 4650 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4640		235 SX
SURF	8.625	223		165 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/31/2017 9:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: PETER FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
8 5/8" surface casing set at 223' w/165 sx cement.  
4 1/2" production casing set at 4640' w/235 sx cement.  
TD 4650 PBTD 4594'.  
Port Collar set at 2435' w/475 sx cement.  
Perforations: 4168' - 4173' and 4084' - 4089'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/31/2017 1:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4500' and pumped 90 sx cement w/350 # hulls. Pulled tubing to 2800' and pumped 90 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 90 sx cement. Cement circulated to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 20 sx cement. Connected to 8 5/8" surface casing with immediate pressure to 300 psi.

GPS: 38.97314N -101.09660W

Perfs:

Top	Bot	Thru	Comments
4169	4174		
4168	4173		
4085	4090		
4084	4089		

KCC WICHITA  
AUG 24 2017  
RECEIVED

Remarks: GLOBAL OILFIELD SERVICES TICKET # 3067 HURRICANE SERVICES RIG

Plugged through: TBG

INVOICED  
SEP 01 2017

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

AUG 03 2017