

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21784-00-02
Spot: SWSENE Sec/Twnshp/Rge: 3-7S-19W
2310 feet from N Section Line, 990 feet from E Section Line
Lease Name: BELLERIVE "P" Well #: 1
County: ROOKS Total Vertical Depth: 3550 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3549		200 SX
SURF	8.625	254		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/03/2017 10:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 385 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Casing leaks at 1000' - 1300'.
1500' to surface w/275 sx cement.
Production perforations: 3257' - 3418'

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/03/2017 12:40 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3248' and pumped 80 sx cement w/200 # hulls. Pulled tubing to 2270' and pumped 80 sx cement w/200 # hulls. Pulled tubing to 1090' and pumped 205 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing with 20 sx cement. Visually checked 8 5/8" x 4 1/2" annulus and cement was to surface.

GPS: 39.47492N -099.41962W

Perfs:

Top	Bot	Thru	Comments
3257	3261		

KCC WICHITA
AUG 24 2017
RECEIVED

Remarks: GLOBAL CEMENTING TICKET # 3070

Plugged through: TBG

INVOICED
SEP 01 2017

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

AUG 03 2017