

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23164-00-00
Spot: SESEWNNE Sec/Twnshp/Rge: 36-10S-23W
1300 feet from N Section Line, 1460 feet from E Section Line
Lease Name: MCCALL Well #: 1-36
County: GRAHAM Total Vertical Depth: 4090 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: PO BOX 8050
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4088		200 SX
SURF	8.625	219		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2017 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TODD A. BROWN Company: RUSSELL OIL, INC. Phone: (785) 445-6270

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 11 sx gel and 500 # hulls.
Perforations at 3620' - 3624' and 3694' - 3698'.
Port Collar at 1777' with 200 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2017 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3635' and pumped 11 sx gel followed by 75 sx cement w/250 # hulls. Pulled tubing to 1825' and pumped 190 sx cement. Cement circulated. Pulled tubing out. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.

GPS: 39.14309 -099.83385

Perfs:

Top	Bot	Thru	Comments
3694	3698		

KCC WICHITA
AUG 24 2017
RECEIVED


Remarks: QUALITY CEMENT TICKET # 354

Plugged through: TBG

INVOICED
SEP 01 2017

District: 04

Signed



(TECHNICIAN)

CM

AUG 03 2017