

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-02038-00-00  
Spot: NESESE Sec/Twnshp/Rge: 30-20S-13W  
990 feet from S Section Line, 330 feet from E Section Line  
Lease Name: MCGREEVEY Well #: 3  
County: BARTON Total Vertical Depth: 3360 feet

Operator License No.: 34278  
Op Name: SHAWN D. EVANS INC. DBA ACE OIL C  
Address: 18529 WALTERS RD PO BOX 606  
RUSSELL, KS 67665

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 5.5   | 3360       |             | 125 SX   |
| SURF   | 8.625 | 140        |             | 235 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/21/2017 12:00 PM  
Plug Co. License No.: 34803 Plug Co. Name: ACE OIL WELL SERVICE, LLC  
Proposal Rcvd. from: SHAWN EVANS Company: SHAWN D. EVANS INC. DBA ACE Phone: (785) 324-0502

Proposed  
Plugging  
Method:

Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 1400 # gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/21/2017 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 760' and 150'. Ran tubing to 3240' and pumped 14 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 60 sx cement w/200 # hulls. Pulled tubing to 800'. Circulated cement to surface with 100 sx cement on casing. Shut in casing and circulated cement to surface on surface pipe with 40 sx cement. Pulled tubing. Topped off with 35 sx cement.

GPS: 38.27791 -0983.79417

Perfs:

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

KCC WICHITA  
AUG 24 2017  
RECEIVED

INVOICED  
SEP 01 2017

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

AUG 03 2017

Form CP-2/3