

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23411-00-00
Spot: SENESENW Sec/Twnshp/Rge: 29-7S-22W
1680 feet from N Section Line, 2440 feet from W Section Line
Lease Name: WEBB Well #: 2-29
County: GRAHAM Total Vertical Depth: 3850 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 200 W DOUGLAS AVE #725
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3845		165 SX
SURF	8.625	221		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/01/2017 9:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: ERIK HAGANS Company: VINCENT OIL CORPORATION DBA Phone: (620) 388-5858

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 3524' - 3527', 3670' - 3676', 3684' - 3686' and 3700' - 3705'.
Port Collar at 1682' w/200 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/01/2017 12:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3507' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 2557' and pumped 75 sx cement w/50 # hulls. Pulled tubing to 1490' and pumped 110 sx cement. Cement circulated. Pulled tubing out. Topped off casing with 10 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 200 psi.

GPS: 39.41819 -09979954

Perfs:

Top	Bot	Thru	Comments
3700	3705		
3670	3676		

Remarks: QUALITY CEMENT TICKET # 277

Plugged through: TBG

District: 04

Signed _____

Marvin Mills
(TECHNICIAN)

CM

KCC WICHITA

AUG 24 2017

RECEIVED

INVOICED

SEP 01 2017

AUG 03 2017