

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Stafford County, Sec. 2 Twp. 21 Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines SE SW SE
Lease Owner Larry G. Stephenson
Lease Name Salem Well No. 2
Office Address 340 Farm Credit Banks Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil 67202
Date well completed 10
Application for plugging filed 10
Application for plugging approved 10
Plugging commenced Nov. 26 10 73
Plugging completed Nov. 29 10 73
Reason for abandonment of well or producing formation depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 10
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 3578 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	286'	8 5/8"	286'	none
		0	3509'	4 1/2"	3509'	2059.50

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 3480' and dumped 4 sacks of cement.
Sun Cementing Company plugged well pumping in 2 sacks of hulls, 10 sacks of mud and 100 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON ss.
Evelyn Roth (employee of owner) or (owner-or-operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 5th day of December 19 73

My commission expires Feb. 10, 1975
George A. Meyer Notary Public


KANSAS GEOLOGICAL SOCIETY
5th Floor Murdock
Wichita, Kansas

15.185.20319.0000

2-21-12W
SE SW SE

MAR 6 1971

DRILLERS LOG



No. 2 Salem

DESCRIPTION:

SR SW SE
2-21S-12W
Stafford County,
Kansas

KANSAS GEOLOGICAL SOCIETY
5th Floor Murdock
Wichita, Kansas

6 5/8" @ 286'
w/275 sx cement

4 1/2" @ 3509'
w/300 sx cement

TOTAL DEPTH: 3578'

COMPANY: L. V. (Stan) Bell

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: December 15, 1970

COMPLETED: December 23, 1970

ELEVATION: 1830' KB

P 15 BOPD + 35' water
GR 29 *Jamaica*

FORMATION

FROM TO

REMARKS

Sand	0	170
Sand & Red Bed	170	287
Shale	287	602
Anhydrite	602	625
Shale & Shells	625	1245
Shale & Lime	1245	1840
Lime w/Shale Strake	1840	1940
Shale & Lime	1940	2915
Lime	2915	3120
Lime & Shale	3120	3230
Lime	3230	3475
Lime & Shale	3475	3578

Sample Log
Anhydrite 602
Halber 3050
Jaranto 3069
Dampas 3082
Br. Lime 3188
LKC 3200
ERC 3438
Conglomerate 3532

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1973
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 28th day of December, 1970.



Virginia K. Albert
Notary Public

My Commission Expires:
July 23, 1974