

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 2 Twp. 21 Rge. 11 (A) W (W)

Location as "NE/CNW%SW%" or footage from lines NW NE SW

Lease Owner F. G. Holl

Lease Name Rugan "E" Well No. 1

Office Address 6427 East Kellogg, Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 21 19 62

Application for plugging filed August 21 19 62

Application for plugging approved " " 19 62


Plugging commenced August 21 19 62

Plugging completed August 21 19 62

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. W. L. Lackamp

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3425 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 200'; set wooden plug
1/4 sack and 20 sacks cement thru drill pipe
filled hole to 35' with mud; set wooden plug-
1/4 sack hulls and 10 sacks cement;
plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1962

CONSERVATION DIVISION
Wichita, Kansas

8-22-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Duke Drilling Co.
Address Box 823, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
L. O. Chubb (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Box 823, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of August, 19 62.

My commission expires 3-1-66

Shirley V. Maier
Shirley V. Maier Notary Public.

INVOICED

DATE 8/22/62

INV. NO. 5574-W

W E L L L O G

Date Commenced: August 12, 1962
Date Completed: August 21, 1962

F. G. Holl
RUGAN "E" - 1
NW NE SW -Sec 2-21-11w
Stafford County, Kansas

0	-	50	Surface Sand
50	-	187	Sand & Clay
187	-	467	Red Bed
467	-	486	ANHYDRITE
486	-	735	Red Bed
735	-	1100	Shale Shells
1100	-	1200	Salt & Shale
1200	-	2110	Lime Shale
2110	-	2515	Shale Shells
2515	-	2808	Shale & Lime
2808	-	2930	Lime & Shale
2930	-	2950	Shale HEEBNER
2950	-	2963	Lime TORONTO
2963	-	3065	Shale & Sand DOUGLAS
3065	-	3085	Lime Shale BROWN LIME
3085	-	3334	Lime LANSING
3334	-	3378	CONGLOMERATE Cherty
3378	-	3405	Shale & Sand SIMPSON
3405	-	3425	Dolomite ARBUCKLE
3425	-		RTD

ELEVATION: 1765 K.B.

FORMATION DATA	
Heebner	2930
Toronto	2950
Brown Lime	3065
Conglomerate	3334
Simpson	3378
Arbuckle	3405
RTD	3425

SURFACE PIPE: Set 274' of
8-5/8" casing @ 272' with
215 sacks cement.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

L. O. Chubb, of lawful age, does swear that the facts
and statements herein contained are true and correct to the best of
his knowledge.

L. O. Chubb
L. O. Chubb

Subscribed and sworn to before me this 21st day of August, 1962.

Shirley V. Maier
Shirley V. Maier-NOTARY PUBLIC

My Comm. Expires: 3-1-66.

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1962
CONSERVATION DIVISION
Wichita, Kansas