

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-185-22,685.0000

LEASE NAME Rugan D

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 5

4290 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR F.G. Holl Co

SEC. 2 TWP. 21 SRGE. 11 (XXX)(W)

ADDRESS P O Box 780167 Wichita, Ks. 67278-0167

COUNTY Stafford

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 3-11-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-14-94

The plugging proposal was approved on \_\_\_\_\_ (date)

by Dodge City Office (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3460

Perfs:3344-3378

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	275	8 5/8	275	0
		0	3456	4 1/2	3456	1798-42 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

3-11-94: Rigged up, dumped 2 bbls. of sand, sand at 3285 ft, dumped 4 sx. cement on top.

3-14-94: Shot off casing at 1920, did not come loose, 2nd shot at 1798, pulled 42 jts. of casing from 1798 ft.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address P O Box 847 Pratt, Kansas 67124


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (Employee of Pratt Well Service, Inc.)  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Pratt Well Service, Inc.



SUBSCRIBED AND SWORN TO before me this 17th day of March, 1994

Dorothy M. Furgason  
 Notary Public

My Commission Expires February 6, 1997

## STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG -----Rugan D #5

Located: SW NW NE, Section 2-T21S-R11W, Stafford Co.,  
Kansas.

OWNER: F. G. Holl Company

ROTARY DRILLING COMPANY: Sterling Drilling Company

COMMENCED: June 11, 1990

COMPLETED: June 15, 1990

LOG

0 - 180' sand & gravel  
180 - 277' red-bed  
277 - 1285' red-bed  
1285 - 3460' shale & lime

CASING RECORD

Ran 6 joints 8 5/8" 24# new casing.  
262.08' pipe set at 275' KB. Cemented  
with 225 sacks 60/40 Pozmix W/ 2% gel  
& 3% cc. Plug down at 11:30AM 6-11-90  
by HOWCO. Good returns to surface.

Ran 84 joints 4 1/2" new & used casing.  
3445.78' pipe set at 3456' KB. Cemented  
with 20 bbl. salt flush, 500 gallons  
super flush, 50 sacks Lite cement  
followed with 125 sacks 50/50 Pozmix  
W/ 125 sacks 50-50 Pozmix W/ regular  
F. G. Holl additives. Plug down at 12:35  
AM 6-15-90 by Howco. Centralizers on  
joints 1, 4 & 10. Shoe joint 11.75'.  
Used 300.08' of used casing.

## DEVIATION SURVEYS:

3387' - 3/4°  
3460' - 1/8°

**RECEIVED**

KANSAS CORPORATION COMMISSION

FEB 04 1994

CONSERVATION DIVISION  
WICHITA, KS