

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 S. Market, Room 2078/ED
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-200540001

LEASE NAME Wright "CB"

WELL NUMBER 1

4670 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 31 TWP. 21S RGE. 24W (E) or (W)

COUNTY Hodgeman

Date Well Completed 1968

Plugging Commenced 6-30-98

Plugging Completed 7-1-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

JUL 10 100R
6-10-98
CONSERVATION DIVISION
Wichita, Kansas

EASE OPERATOR K & N Petroleum, Inc.

ADDRESS 513 W. 6th Ellinwood, Kansas 67526

PHONE (316) 564-3908 OPERATORS LICENSE NO. 3208

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

This plugging proposal was approved on _____ (date)

by Mike Meyers (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4580'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	524'	None
				5-1/2"	4576'	1500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each side. Plugged off bottom with sand to 4430' and 5 sks. cement, Shot casing @2400', 2200', 2000', 1800', 1600' and 1500'. Pumped 10 sks. gel and 50 sks. cement @1500', pulled to 700', pumped 40 sks. cement, pulled to 530', pumped 50 sks. cement, pulled to 40' and circulated cement to top. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: K & N Petroleum, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 8th day of July, 19 98

[Signature]
Notary Public

My Commission Expires: _____

