

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-055-21733-00-00

LEASE NAME Hutchinson

WELL NUMBER 102

1250 Ft. from S Section Line

1250 Ft. from E Section Line

SEC. 32 TWP. 21S RGE. 34 (E) or (W)

COUNTY Finney

Date Well Completed 3/6/01

Plugging Commenced 4/16/02

Plugging Completed 4/16/02

RECEIVED

MAY 06 2002

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

KCC WICHITA

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS 1579 E. 21st, Tulsa, OK 74114

PHONE# 918 742-5531 OPERATORS LICENSE NO. 5293

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/31/02 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Chase Depth to Top 2527 Bottom 2568 T.O. 2735

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Chase	Gas	0	2678	5 1/2	3-6-01	None
		0	308	8 5/8	3-4-01	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

Pumped 400# hull slurry - Pumped 25 sacks Class "H" cement 2568' to 2347'

Pumped 9# gel spacer from 2347' to 1247', Pumped 173 sacks Class "H" cmt from 1247' to surf.

Name of Plugging Contractor Sargent Plugging Service License No. 31151

Address Rt. 1 Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Sharon LaValley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Sharon LaValley

(Address) 1579 E. 21st, Tulsa, OK 74114

SUBSCRIBED AND SWORN TO before me this 1<sup>st</sup> day of May, 19 2002

Amy Warren  
Notary Public

My Commission Expires: 4/9/05



OR