

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-055-20235.0000

LEASE NAME Norris

WELL NUMBER 1-31

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

1324 Ft. from S Section Line

3867 Ft. from E Section Line

SEC. 31 TWP. 21SRGE. 34 (X) or (W)

LEASE OPERATOR Colorado Interstate Gas Exploration

ADDRESS P. O. Box 749 Denver, CO 80201-0749

COUNTY Finney

PHONE# (303) 573-4482 OPERATORS LICENSE NO. 06594

Date Well Completed 11/16/76

Character of Well Gas

Plugging Commenced 6/28/93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/29/93

The plugging proposal was approved on 6/25/93 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Krider Depth to Top 2602' Bottom 2610' T.D. 2990'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|---------------|-----------|------|-------|--------|--------|------------|
| Council Grove | Gas/Water | 0 | 597' | 8-5/8" | 597' | 0' |
| Krider | Gas | 0 | 2988' | 4-1/2" | 2988' | 0' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set CIBP @ 2550' & cap w/20' cmt. Perforate 1040'. Mix & pump 210 sx 65/35 Poz w/6% gel down 4-1/2" casing and 210 sx down 8-5/8" x 4-1/2" annulus. Witnessed by KCC representative, Glen Barlow, on 6/29/93. Cut off casing 4' below ground level. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor N/A (plugged by Operator) License No. _____

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Colorado Interstate Gas Exploration

STATE OF Colorado COUNTY OF Denver, ss.

John D. Perry (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 749 Denver, CO 80201-0749

SUBSCRIBED AND SWORN TO before me this 21st day of July 1993.

Sareen Hurst
 Notary Public

My Commission Expires: June 7, 1995

RECEIVED 93.
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas
 Form CP-4
 Revised 05-88