

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-009-00493-00-00

WELL PLUGGING RECORD

File 138-9

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 31 Twp. 16S Rge. 12W (EX) (W)  
Location as "NE/CNW/SW" or footage from lines SE/4 NE/4 SE/4  
Lease Owner Veeder- Producers- Colorado  
Lease Name Charles Geopetras Well No. 1  
Office Address \_\_\_\_\_  
Character of Well (completed as Oil, Gas or Dry Hole) OTL  
Date well completed 8-30-55 19\_\_  
Application for plugging filed Oct 21 1958  
Application for plugging approved Oct 22 1958  
Plugging commenced October 22 1958  
Plugging completed October 28 1958  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production Unknown 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Truin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3150 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with gravel to 3140'. Dumped 5 sacks of cement. Shot pipe off at 2543'. Pulled pipe and mudded hole to 230'. Dumped 25 sacks of cement after setting rock bridge. Mudded to 40'; set another rock bridge and dumped 10 sacks of cement at base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self  
Address R R #4 Hutchinson, Kansas

STATE OF Kans. COUNTY OF Reno, ss. Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self  
R. R. #4, Hutchinson, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of November, 19 58

My commission expires August 12, 1961


Notary Public  
21 1958

PLUGGING  
FILE SEC. 31 T. 16 R. 12W  
BOOK PAGE 138 LINE 9

CONSERVATION DIVISION  
Wichita, Kansas

15-009-00493-00-00

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Well 138-9

Drilled for Veeder Supply & Dev'l. Co., North American  
Gas Corp., Producers Pipe & Supply Co. Farm Charles No. 1 Depth 1450'  
 Contractor Veeder Supply & Dev'l. Co. Pipe 4 5/8" cas. cemented w/150 sacks cement  
4 1/2" cas. cemented w/150 sacks cement  
 Location RR/A RR/A SW/4 Sec. 11 Twp. 16S Range 12W  
 Commenced 8-19-1955 Completed 8-30-1955 County Barton State Kansas

Clay and lime shales	0	45	45	TOPS:	
Gray shale	45	60	15	All depths from: EB 6' above ground	
Shale and lime streaks	60	256	196	Topoka	2906
Shale	256	355	99	Hoebner	3047
Sand, pyrite, iron streaks	355	475	120	Brown Line	3135
Shale, streaks iron	475	580	105	Lansing EC	3149
Shale, red bed	580	835	255	Top Arbuckle	3397
Anhydrite	835	855	20		
Shale and shales	855	1495	640		
Shale and lime	1495	2075	1380		
Lime	2075	3080	205		
Shale lime	3080	3165	85		
Lime	3165	3415	250		
Arbuckle	3415	3450	35		
P. U.	3450				

**PLUGGING**  
 FILE SEC. 31 T. 16 R. 12W  
 BOOK PAGE 138 LINE 9

AFFIDAVIT

STATE OF KANSAS )  
Montgomery County ) SS

Leo C. Veeder, of lawful age, being first duly sworn on oath, deposes and says:

THAT he is a resident of Cherryvale, Montgomery County, Kansas; that he knows and on oath hereby states that the above drilling log covering the Charles #1 well located in Section 11-16S-12W, Barton County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.  
By Leo C. Veeder  
Leo C. Veeder

Subscribed and sworn to before me this 2nd day of September, 1955.

CONSERVATION DIVISION  
 Wichita, Kansas  
 SEP 21 1958  
 [Signature]  
 Notary Public

My commission expires July 11, 1956.