

State of Kansas



15.185.13141.0000

FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

4-19-1963

RECEIVED
 STATE CORPORATION COMMISSION

APR 19 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Perry Daniels of Central Pipe Pulling has this date requested permission to plug the following described well:

Mr. Daniels guarantees payment of the plugging fee.

Operator's full Name: Fred Asbury

Complete Address: 161 West Fourth, Hoisington, Kansas

Lease Name: Robl Well No. # 2

Location: NW NW NE Sec. 2 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3413 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Daniels was instructed to plug the well as follows:

- 277' of 8 5/8" surface pipe cemented with 310 sacks.
- 3409' of 5 1/2" long string. Fill hole to 200', 10' rock
- bridge cement with 20 sacks. fill hole with mud to 40',
- 10' rock bridge cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent